

#### Sonja Winkelmann, Senior Director, Net Zero Energy Housing, CHBA

Chris Williams, Vice President, Avalon Master Builder

MEET OUR DAY 1 CO-HOSTS!

## Land Acknowledgement

We acknowledge that the land where the Richmond Neighborhood is located rests on the traditional territories of the Musqueam, Squamish, and Tsleil-Waututh.

We also acknowledge the systemic policies of genocide, relocation, and assimilation that still impact many Indigenous families today.

As settlers and guests on these lands we respect the work of Native Nations, leaders, and families, and make ongoing efforts to center Indigenous knowledge, creativity, and resilience.



# Building Codes

# Builders

## The Diffusion of Innovations



#### THE PREDICAMENT OF KNOWLEDGE

- Innovators & early adopters are the holders of the most current knowledge.
- To be able to "cross the chasm" we must disseminate this knowledge, shortening the learning curve and paving the way for the early majority.
- The challenge is to effectively apply what we already know and what we continue to learn, en masse.













## VS.





## Where are you from?



## Who are you?



# What do you want to get out of the event?

214 responses



## Day 1 Agenda

Find it online at www.chba.ca/nzls

8:30 AM CATALYZING PREFABRICATION THROUGH DESIGN to achieve higher performance in housing.

10:15 AM Break and networking in the DEMO HUB

**10:45 AM FINDING THE EMISSIONS SWEET SPOT. How much is too much?** 

- 12:00 PM Lunch Buffet and networking in the DEMO HUB
- 1:15 PM WHO'S DOING WHAT? And is it enough to get us there?
- 2:30 PM Break and networking in the DEMO HUB
- **3:00 PM SAFE HAVENS. Protecting our assets and our families.**

4:15 PM Day 1 wrap-up

5:00 PM – Cocktails and buffet dinner, Open Mic, "High Performance Brain"

9:15 PM auction, and networking in the DEMO HUB



Access the speaker info online here:





Access the full agenda online here:



## CATALYZING PREFABRICATION THROUGH DESIGN to achieve higher performance in housing.

Kevin Lee CEO, CHBA Keith Herring Director, Modular & Construction Systems, CHBA

-----

de (15 11 - IN

Mike Schmidt President, Auto Construct Incorporated

- ----

П

Chris Williams Vice President, Avalon Master Builder

-

Neil Hawkins Development Manager, Avalon Master Builder



## Kevin Lee, CEO, CHBA

# Builders/Renovators: Have you tried any level of prefabrication?



## What have you worked with?



# Do you believe prefab could help build more affordable housing?



# Do you believe prefab could help build more energy efficient and climate resilient housing?



# Do you believe prefab could help you build better, faster, and cheaper?





Keith Herring, Director, Modular and Construction Systems, CHBA

#### Modular Construction Council Strategic Plan

- Sector Transition Strategy B2G and B2B, automation, multi-family modular, panels, industry and municipal awareness
- Recognition of the carbon impact
- Application for funding for transition HUB for factory built is being completed in summer 2024

## Sector Transition Strategy HUB

- What can we do?
- Facilitate education, training and transition, building officials
- Provide Soft Cost financing, infrastructure Investments, tax incentives, distribute funds for other subsidiary and supplier industries

## **CHBA SECTOR TRANSITION STRATEGY**

Canadian Home Builders' Association



SECTOR TRANSITION STRATEGY

Solutions to the barriers preventing Canada from building 5.8 million homes







#### **GETTING TO 5.8** MILLION HOMES

Accomplishing the goal of doubling housing starts is a complex matter that is not achievable with the current status quo. To do it, we need a whole-systems approach by all governments at the local, provincial and federal level.

Canada's housing industry cannot build 5.8 million homes without the government supporting systemic change in four areas: financial, policy, labour, and productivity.

CHBA's Sector Transition Strategy builds on and relies on enactment of CHBA's recommendations to address housing affordability and supply to create the environment where housing production can actually increase. It then focuses on supporting and de-risking an industry transition to incorporated more factory-built systems in order to increase productivity with the goal of addressing Canada's 3.5 million housing unit supply deficit.

**Continue federal** leadership but ensure a holistic approach

**Remove barriers to** homeownership for first-time buyers

Lower government-imposed costs that add to affordability challenges

**Remove barriers within** the home building process

Avoid adding costs through codes and regulations

Address labour shortages Support increased productivity

03 CHBA'S SECTOR TRANSITION STRATEGY



#### HOW GOVERNMENT CAN SUPPORT **CHBA'S SECTOR TRANSITION STRATEGY** FOR HOUSING SUPPLY

There are concrete steps the government can take to help to address Canada's housing crisis and improve housing affordability through the increased productivity of factory-built solutions. The actions on on this page came from input and feedback from builders across the country, including critical insight from CHBA's Modular Construction Council, which is made up of representatives from many of Canada's current factories. The pyramid on this page and the next is a made-in-Canada plan that will allow for the residential construction sector to transition to more factory-built homes to increase housing supply and build 5.8 million homes to close the supply deficit. It is modelled after Canada's Plan for a Clean Economy, as clean technology faces similar market penetration challenges. Just as the government stepped forward in Budget 2023 to address the climate crisis with a made-in-Canada plan for a clean economy. Canada needs a made-in-Canada plan for housing supply, using similar tools.

10 | CHBA'S SECTOR TRANSITION STRATEGY





**Canadian Home Builders' Association** 141 Laurier Avenue West, Suite 500 Ottawa, ON K1P 5J3



www.chba.ca | @CHBANational

## **Keith Herring**

**CALL TO ACTION** 

Director, Modular & Construction Systems

#### **Canadian Home Builders' Association**

289.251.0754 | keith.herring@chba.ca



Email me to discuss your needs and how to be part of the Sector Transition Strategy HUB! Download the Sector Transition Strategy www.chba.ca/sectortransition







Mike Schmidt, President, Auto Construction Incorporated

## **The Prefabrication Journey**

## Start with a Strong Foundation







www.autoconstruct.ca

#### What is your business objective?





#### What form of prefabrication is best for your application?







Production Capacity Manufacturing Footprint Design Flexibility Standard Freight Speed of Construction System Integration Remote Work Inclement Weather



#### You don't need a factory to get started.

Use the "Book-End Strategy".

#### **Take Control**





#### **Get Traction**



Design for Manufacturing and Assembly Manufacturing Facility

#### **Field Execution**



#### **The Point of Diminishing Returns**



www.autoconstruct.ca

#### **Begin with the end in mind.**





#### "Onsite assembly informs offsite manufacturing."







#### Thank you



Mike Schmidt

mike.schmidt@autoconstruct.ca +1 780 964 1479





## Chris Williams, Vice President, Avalon Master Builder

Adoption of Technology to

build repeatable and more

cost-effective homes









### This is the same blender...







#### This is the same house...







- 2X6 EXTERIOR WALL @PARTY WALL 60min. FRR W5 • exterior cladding as per elevations / Material Chart installed as per manufacturer's specifications
  - 3/8" plywood or OSB sheathing vertical strapping @16" o.c. (at exterior panel cladding locations only)
  - 1 1/2" continuous XPS insulation
  - 1 layer vapour permeable building paper, 30 min. or equiv., installed as per manufacturers specifications • 5/8" Type-X gypsum sheathing, extended over rim board
  - 2x6 wood studs spaced as per structural engineer R24 batt insulation
  - air space
  - 2x4 wood studs, on flat
  - inside edge to line up w/inside edge of adjacent interior party wall fibreglass or mineral wool batt insulation
  - 1 layer vapour permeable building paper • 5/8" Type X gypsum board (to be continuous behind all abutting partitions;
  - all penetrations must be sealed with firestop sealant) • 1/2" standard or mold-resistant gypsum board

nome



-Framing Dimensions

w/ general assembly

notes

-Detailed wall

assembly up to carpenter

-Termination locations

for Plumbing and HVAC

-Detailed *plumbing* and heat run up to mech trade



#### HVAC DRAWING KEY NOTES: (#)

- S/A FLOOR GRILLE. (S/A DUCT RUNNING IN FLOOR BELOW)
- 4"Ø DRYER EXHAUST UP TO ROOF. INSTALL ROOF TERMINATION AS PER DRYER MANUFACTURER RECOMMENDATIONS. 4"Ø EXHAUST. DUCT TO HRV 3.
- 5"Ø SUPPLY AIR DUCT UP TO FLOOR GRILLE ABOVE. 4"Ø SUPPLY AIR DUCT UP TO FLOOR GRILLE ABOVE.
- RETURN AIR FROM ABOVE.
- RUN DUCT THROUGH JOISTS. COORDINATE WITH STRUCTURAL AND ARCHITECTURAL.
- EXHAUST WALL CAP C/W BACKDRAFT DAMPER.
- SUPPLY GRILLE AT CEILING.
- DRYER EXHAUST. INSTALL WALL CAP AS PER DRYER MANUFACTURER RECOMMENDATIONS.
- 11. HRV INTAKE TERMINATION. INSTALL AS PER HRV MANUFACTURER RECOMMENDATIONS.
- 12. OUTDOOR UNIT FOR HP-1. RUN REFRIGERANT LINES BETWEEN THE UNITS. REFER TO MANUFACTURER INSTALLATION MANUAL FOR REFRIGERANT PIPING RUNS AND UNIT CLEARANCES.
- 13. HRV EXHAUST TERMINATION, INSTALL AS PER HRV MANUFACTURER **RECOMMENDATIONS**
- 14. 5"Ø EXHAUST DOWN TO HRV ON MAIN FLOOR
- 15. 5"Ø EXHAUST FROM WASHROOMS ON TOP FLOOR



#### PLUMBING DRAWING KEY NOTES: (#)

- 1/2" HOT AND COLD WATER FROM BELOW.
- 1/2" COLD WATER FROM BELOW. 2.
- "HOT AND COLD WATER UP. 3.
- K" COLD WATER UP. 4
  - 5 4"Ø OVERHEAD SANITARY DOWN TO FLOOR BELOW.
  - 6 4"Ø SANITARY RISER FROM TOP FLOOR.
  - 4"Ø SANITARY DOWN TO UNDER SLAB.
  - #Ø HOT AND COLD WATER LINES FOR TOP FLOOR.
  - 9 1"Ø COLD WATER FROM WATER METER ROOM.
  - 10. PROVIDE LAUNDRY BOX WITH SANITARY, HOT AND COLD WATER OUTLETS AND WATER HAMMER ARRESTORS - OATEY MODEL QUADRO OR EQUIVALENT
  - JOB H&C WATER DOWN TO FLOOR ASSEMBLY FOR KITCHEN SINK. 11.
  - 12. 1"Ø COLD WATER FROM UNDER SLAB FOR BASEMENT UNIT
  - 1"Ø COLD WATER FROM UNDER SLAB FOR UPPER UNIT 13.



6/27/2024



- W5 2X6 EXTERIOR WALL @PARTY WALL 60min. FRR
   exterior cladding as per elevations / Material Chart installed as per manufacturer's specifications
  - 3/8" plywood or OSB sheathing vertical strapping @16" o.c. (at exterior panel cladding locations only)
  - 1 1/2" continuous XPS insulation
  - 1 layer vapour permeable building paper, 30 min. or equiv., installed as per manufacturers specifications
     5/8" Type-X gypsum sheathing, extended over rim board
  - 2x6 wood studs spaced as per structural engineer
     x24 batt insulation
  - air space
  - 2x4 wood studs, on flat
  - inside edge to line up w/inside edge of adjacent interior party wall o fibreglass or mineral wool batt insulation
  - 1 layer vapour permeable building paper
    5/8" Type X gypsum board (to be continuous behind all abutting partitions;
  - all penetrations must be sealed with firestop sealant)





-Framing Dimensions w/

general assembly

notes

- -Detailed wall assembly
- up to carpenter
- -Termination locations
- for *Plumbing* and *HVAC*
- -Detailed plumbing and

heat run locations up to

#### mech trade partner



#### HVAC DRAWING KEY NOTES:

- 1. S/A FLOOR GRILLE. (S/A DUCT RUNNING IN FLOOR BELOW)
- 2. 4"Ø DRYER EXHAUST UP TO ROOF. INSTALL ROOF TERMINATION AS PER DRYER MANUFACTURER RECOMMENDATIONS.
- 4"Ø EXHAUST. DUCT TO HRV.
- 5"Ø SUPPLY AIR DUCT UP TO FLOOR GRILLE ABOVE.
- 4"Ø SUPPLY AIR DUCT UP TO FLOOR GRILLE ABOVE.
- . RETURN AIR FROM ABOVE.
- 7. RUN DUCT THROUGH JOISTS. COORDINATE WITH STRUCTURAL AND ARCHITECTURAL.
- 8. EXHAUST WALL CAP C/W BACKDRAFT DAMPER.
- 9. SUPPLY GRILLE AT CEILING.
- 10. DRYER EXHAUST. INSTALL WALL CAP AS PER DRYER MANUFACTURER RECOMMENDATIONS.
- 11. HRV INTAKE TERMINATION. INSTALL AS PER HRV MANUFACTURER RECOMMENDATIONS.
- 12. OUTDOOR UNIT FOR HP-1. RUN REFRIGERANT LINES BETWEEN THE UNITS. REFER TO MANUFACTURER INSTALLATION MANUAL FOR REFRIGERANT PIPING RUNS AND UNIT CLEARANCES.
- HRV EXHAUST TERMINATION. INSTALL AS PER HRV MANUFACTUREF RECOMMENDATIONS.
- 14. 5"Ø EXHAUST DOWN TO HRV ON MAIN FLOOR
- 15. 5"Ø EXHAUST FROM WASHROOMS ON TOP FLOOR.



#### PLUMBING DRAWING KEY NOTES: (#)

- . 🔏 HOT AND COLD WATER FROM BELOW.
- 2. 1/2" COLD WATER FROM BELOW.
- 3. 🔏 HOT AND COLD WATER UP.
- 4. 1/2" COLD WATER UP.
  - 5. 4"Ø OVERHEAD SANITARY DOWN TO FLOOR BELOW.
  - 6. 4"Ø SANITARY RISER FROM TOP FLOOR.
  - 7. 4"Ø SANITARY DOWN TO UNDER SLAB.
  - 8.  $\frac{3}{4}$ "Ø HOT AND COLD WATER LINES FOR TOP FLOOR.
  - 9. 1"Ø COLD WATER FROM WATER METER ROOM.
  - 10. PROVIDE LAUNDRY BOX WITH SANITARY, HOT AND COLD WATER OUTLETS AND WATER HAMMER ARRESTORS - OATEY MODEL QUADRO OR EQUIVALENT
  - 11. <sup>1</sup>/<sub>2</sub>"Ø H&C WATER DOWN TO FLOOR ASSEMBLY FOR KITCHEN SINK.
  - 12. I"Ø COLD WATER FROM UNDER SLAB FOR BASEMENT UNIT.
  - 13. 1"Ø COLD WATER FROM UNDER SLAB FOR UPPER UNIT.





# Avalon BHAG



Investment in technology to create a repeatable approach to building homes while delivering an EBITDA of \$X per year with leadership engagement and profit sharing.

What we have determined thus far (BIM)...



## **Building Information Modeling (BIM) Details**









6/27/2024

## **Building Information Modeling (BIM) Details**

Collaborative Design

- Collaboration among all stakeholders
- Centralized platform reduces the likelihood of errors and discrepancies

**Spatial Coordination** 

Design stage clash detection and resolution

**Quantifications and Estimates** 

Precise fitment of scopes allow automated quantity takeoffs





## BIM – Comes with Instructions

We determine the "how to" for framing

- Most efficient use of lumber is predetermined
- Most efficient assembly predetermined
- This can extend to all scopes of work (plumbing, mechanical, drywall, etc)







## BIM + Time = 4D

Time-Based (BIM 4D) models allow visualization of construction sequencing

- Simulate and analyze different construction sequences virtually
- Identify the most efficient and cost-effective scheduling options
- Optimize resource allocation







## BIM w/ Augmented Reality

BIM data onto the physical construction site

- Allows visualization of the final construction in the real world
- Provides workers with real-time guidance
- Allows comparison of the physical construction progress against the BIM model
- Enables quick identification of deviations from the original design







## BIM 4D (Time) + Cost = 5D

Integration of detailed cost information with and 4D models

- Accurate quantification of materials, labor, and other resources at each construction stage
- Real-Time cost updates as project progresses
- Detailed cash flow planning







Development Manager, Avalon Master Builder

Neil Hawkins,

## 2024 Net Zero Leadership Summit

CHBA Net Zero Home MURB Pilot - Avalon

# Utilizing Prefabrication to improve project efficiency.

Avalon Master Builder

June 2024









Knock down wall packages

## Types of Pre-fab framing



## Factory built wall panels







#### Factory installed blocking











#### Factory assembled floor cassettes







Factory built floor System installed on Foundation.







#### Factory production line

#### Wall production line









**hóme** 6/27/2024

## 6-unit townhome block Three weeks to complete on-site work





## Thank you!



